




# **Proposed WDM-Based Wideband Photonic RF Bus For The Navy's AMRFS Architecture**

**DARPA WDM WORKSHOP**  
**April 18, 2000**

**Dr. Akis Goutzoulis**  
**Northrop Grumman ESSD**  
**Antenna Department**  
**Microwave Photonics**

Report Documentation Page				Form Approved OMB No. 0704-0188	
Public reporting burden for the collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to a penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number.					
1. REPORT DATE <b>18 APR 2000</b>		2. REPORT TYPE <b>N/A</b>		3. DATES COVERED <b>-</b>	
4. TITLE AND SUBTITLE <b>Proposed WDM-Based Wideband Photonic RF Bus for the Navy's AMRFS Architecture</b>				5a. CONTRACT NUMBER	
				5b. GRANT NUMBER	
				5c. PROGRAM ELEMENT NUMBER	
6. AUTHOR(S)				5d. PROJECT NUMBER	
				5e. TASK NUMBER	
				5f. WORK UNIT NUMBER	
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) <b>Northrop Grumman</b>				8. PERFORMING ORGANIZATION REPORT NUMBER	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)				10. SPONSOR/MONITOR'S ACRONYM(S)	
				11. SPONSOR/MONITOR'S REPORT NUMBER(S)	
12. DISTRIBUTION/AVAILABILITY STATEMENT <b>Approved for public release, distribution unlimited</b>					
13. SUPPLEMENTARY NOTES <b>DARPA/MTO, WDM for Military Platforms Workshop held in McLean, VA on April 18-19, 2000, The original document contains color images.</b>					
14. ABSTRACT					
15. SUBJECT TERMS					
16. SECURITY CLASSIFICATION OF:			17. LIMITATION OF ABSTRACT <b>UU</b>	18. NUMBER OF PAGES <b>15</b>	19a. NAME OF RESPONSIBLE PERSON
a. REPORT <b>unclassified</b>	b. ABSTRACT <b>unclassified</b>	c. THIS PAGE <b>unclassified</b>			

# Photonic RF Bus & the AMRFS Architecture



# The need for a photonic RF Bus




Effective dynamic allocation of wideband multifunction apertures and transmit/receive resources requires an advanced RF interconnection network, with programmable *broadcast*, *multicast*, and *narrowcast* capability.

Coaxial interconnections are point-to-point with little reconfiguration capability (large number of lines and switches required), are lossy and heavy.

*The WDM RF photonic bus offers a wideband, lightweight, fully programmable solution*

# WDM RF Bus: *Architecture*

## Multiplex and Broadcast



## PROPERTIES

- (+) Single fiber to the antennasite
  - (+) Single optical amplifier
  - (+) Expandability is relatively easy
  - (+) Loss grows slow with M plus fixed MUX loss
- $$L \text{ (dB)} = -10 \log M - L_M$$


# Prototype WDM RF Bus Objectives (1998/1999)



**Development and demonstration of a WDM-based photonic RF bus for interconnecting and dynamically allocating multiple subarrays to multiple RF functions.**


Prototype bus specs: *4 RF functions, 16 subarrays, operation over 1-5 GHz, SNR > 150 dB/Hz, SFDR > 110 dB-Hz<sup>2/3</sup>*

# Photonic RF Bus: *Prototype Block Diagram*



**Wavelengths (from ITU grid): 1542.14 nm, 1546.12 nm, 1550.12 nm, 1554.13 nm**  
**Estimated RF Isolation: > 90 dB**



# Photonic RF Bus: *Prototype*






# Photonic RF Bus: *Measured SNR of the Prototype Bus*

Predicted Average SNR: 141 dB/Hz




O.A. to 1542 nm only

O.A. to all wavelengths



# Photonic RF Bus: *COTS Optical Tunable Filters*

**QUEENSGATE (\$ 5.5 k)**




BW: 29.6 nm (vs 14 nm of bus)  
 3 dB Op. BW: 0.15 nm (18.75 GHz)  
 IL: 3.0 dB  
 Speed: 50 nm/ms  
 Voltage: 0-20 V

**DICON (\$ 2.0 k)**




BW: 30 nm (vs 14 nm of bus)  
 0.5 dB Op. BW: 0.6 nm (75 GHz)  
 IL: 1.0 dB  
 Speed: Manual

# Photonic RF Bus: *Channel Isolation (Manual Filter)*




## Manual Filters (Dicon)

- EMI limited measurements
- Excellent reproducibility




# Photonic RF Bus: *Channel Isolation (Electronic Filter)*



Optical reflections ?  
Random generator noise ?

## Electronic Filters (Queensgate)

- EMI limited measurements
- Lossier than Dicon's (by 2 dB)
- Strange "spikes"







# Photonic RF Bus: *Channel Isolation (EMI Isolated)*




## No Filter



## Selected Signal



## Blocked Signal




Output signal (no filter) = -9 dBm

Selected signal (with filter) = -12.8 dBm

Blocked signal = <-110 dBm

**Isolation is better than 97.2 dB**

# Photonic RF Bus Prototype: *CONCLUSIONS*

- 
- COTS-based Photonic RF Bus was designed, fabricated and tested. It performed as expected: **NO SURPRISES**
  - Low cost directly modulated links, moderate cost externally modulated links and low cost receivers were developed and performed very well over the 1-5 GHz band
    - Need to know what "type" of link is appropriate for what "type" of function
    - Further improvements possible by matching the link and function RF responses
  - COTS passive optical components and COTS optical amplifiers have good performance. No need for custom devices

# Photonic RF Bus Prototype: *CONCLUSIONS*



- The optical tunable filters are the key component of the bus.
- The COTS manual tunable optical filters we used performed very well, but are not practical ...
- The electronic tunable filters we used did not perform as well: they were drifting, were lossy, and affected the system Phase Noise

# The Photonic RF Bus needs tunable optical filters ...



## Desired Optical Tunable Filter Specs

- (1) Speed:  $< 1$  msec
- (2) Loss: 1-2 dB (Optical)
- (3) 0.5 dB Optical BW: 0.6-0.5 nm
- (4) Optical Isolation: 50 dB (optical) @ 4 nm from center
- (5) Size: not critical (2-3 in<sup>3</sup> is OK)
- (6) Cost: ~ \$ 1 k
- (7) Control: analog or digital is OK
- (8) No dithering plates please ... they kill the system phase noise.